



Redding Service Station Equipment  
General Engineering & Building Contractors

1515 Charles Dr.  
Redding, CA 96003

Ph: (530) 241-1275  
Fax: (530) 241-1620

# Job Quote

**Quote Number:** 7491  
**Quote Date:** 12/28/2018  
**Customer ID:** 863

**Bill to:** City of Red Bluff  
555 Washington St.  
Red Bluff, CA 96080

**Service at:** City of Red Bluff  
1055 Kimball Rd.  
Red Bluf, CA 96080

Job Description	Price
-----------------	-------

\$13,949.00

**Additional Details:**

CITY OF RED BLUFF  
LIFT REPLACEMENT

**SCOPE OF WORK:**

- 1) Remove existing in ground lift and dispose of offsite. Leave casing in ground.
- 2) Sawcut and remove concrete to allow for new footings for new to post lift.
- 3) Backfill excavation with pea gravel.
- 4) Pour new concrete footings and cap excavation. Finish to match existing
- 5) Furnish and Install new Rotary SPOAION8T0 - Two Post Above ground 10,000 lb assymetrical truck adapter lift.
- 6) Run new electrical and test lift operation

Includes all Labor, Materials, Freight, Equipment and Sales Tax.

\_\_\_\_\_  
Authorized Signature



1515 Charles Dr.  
Redding, CA 96003

Ph: (530) 241-1275  
Fax: (530) 241-1620

# Job Quote

Quote Number: 7491

Quote Date: 12/28/2018

**Bill to:** City of Red Bluff  
555 Washington St.  
Red Bluff, CA 96080

**Service at:** City of Red Bluff  
1055 Kimball Rd.  
Red Bluff, CA 96080

**Description:**

**Customer ID:** 863

Items	Quantity	Unit	Unit Price	Total Price
Lift	1.00		\$4,868.00	\$4,868.00
Equipment Rental	1.00		\$550.00	\$550.00
Concrete, Electrical, Materials	1.00		\$750.00	\$750.00
Labor/Travel	1.00		\$7,450.00	\$7,450.00
Sales Tax	1.00		\$331.00	\$331.00

<b>Quote Subtotal:</b>	<b>\$13,949.00</b>
<b>Estimated Tax:</b>	<b>\$0.00</b>
<b>Quote Amount:</b>	<b>\$13,949.00</b>

**Additional Details:**